

EQUUS PRODUCT SYSTEM REFERENCE SHEET



The prepared concrete is primed with Matacril 108 H primer and then the cracks are repaired using Matacril LM



Matacril waterproofing layer applied



Matacril 215 Wear layer is broadcast with charcoal aggregate



Second and final application of Matacril STC (Clear) Topcoat



Completed carpark

Project Name: The Rocks Apartments

Location: Auckland

Project Type: Carpark — Refurbishment

Project Size: 250sqm

System: Equus Matacril Carpark System
(with Charcoal Aggregate)

Certified Applicator: Solid Floors Ltd

Completion Date: 2025

Equus Industries Ltd

Email: info@equus.nz

Website: www.equus.nz