

Trinity Apartments

RFS32047

DATE: JUN 2022



PROJECT REFERENCE SHEET



Mecano fixing plates with screws at 150mm spacings to mechanically fasten the Deboplast base sheet



Alsan Mastic 2200 sealant to seal DUO cap sheet against aluminium parapet capping



Membrane detailing to timber plinths with skylight cricket diverters completed



Pipe penetrations and short roof vent on plinths



Finished project

Project Type: Renovation

Location: Auckland

Product System: EQUUS SOPREMA DUO Membrane
Mechanically Fastened

Project Size: 1100m²

Certified Applicator: Access / Gunac

Completion Date: 2022