

The Rocks Apartments

RFS44017

DATE: JAN 2025



PROJECT REFERENCE SHEET



The prepared concrete is primed with Matacryl 108 H primer and then the cracks are repaired using Matacryl LM



Matacryl waterproofing layer applied



Matacryl 215 Wear layer is broadcast with charcoal aggregate



Second and final application of Matacryl STC (Clear) Topcoat



Completed carpark

Project Type: Carpark Refurbishment

Location: Auckland

Product System: Equus Matacryl Carpark System (with Charcoal Aggregate)

Project Size: 250m²

Certified Applicator: Solid Floors Ltd

Completion Date: 2025